

Project Overview


- ➤ Construct approximately 5.1 miles of natural gas distribution main along Route 2 in Warwick (620 feet), West Warwick (5,780 feet), and East Greenwich (20,200 feet)
- ➤ 20" steel distribution main will be installed in parallel to existing 12" distribution main in Route 2, Rhode Island Department of Transportation Right-of-Way (RIDOT ROW)
- ➤ Will be constructed to be in-line inspected (ILI) and designed for maximum allowable operating pressure (MAOP) of 200 psig, but initially operated at 99 psig
- Cost: Approximately \$81.3M

Project Need

- Project allows National Grid to:
 - Continue to maintain minimum required pressures to local customers to meet forecasted growth
 - Improve gas system delivery
- Forecasted local customer growth expected to exceed capacity of Southern Rhode Island Distribution System which could result in pressures to local customers falling below minimum in Southern Rhode Island service territory
- Current growth forecasts predict approximately 3,750 local customers could lose service on peak days by Winter 2022/2023
- Without Project, National Grid will need to implement restrictions or a moratorium on new gas services and requests to expand existing services to ensure reliable service to existing customers

Project Location and Schedule

Construction – Phase 1 (12,600')	April – December 2019
Construction – Phase 2 (11,000')	April – December 2020
Construction – Phase 3 (3,000')	April – December 2021



Project Construction

- Project construction will occur in three phases
- Over 90% of Project will be open-cut along western shoulder of Rt. 2
- Six jack-and-bore locations
 - Two in Phase 1
 - Four in Phase 2
- Two horizontal directional drill (HDD) locations at bridge crossings
 - ❖ Near Meadowbrook Road in East Greenwich approximately 700' drill (Phase 2)
 - Route 2/Route 4 Crossing in East Greenwich approximately 1300' drill (Phase 3)

Open-Cut



Source: JMB Construction, Inc.

Jack-and-Bore



Source: Spring & Associates, Inc.

Horizontal Directional Drill



- 1 Directional Drill machine
- 2 Rotating and pressing pipes
- ③ Pilot drill begins ground penetration
- 4 Technician with locator receiver box

- (5) Pilot head drilling and pressing for direction
- 6 Enlargement and pull-back with Reamer
- Swivel attached to Reamer and Pipe
- (8) Utility Pipe being Pulled Back

Source: Northwest Utilities Illinois

General Gas Main Installation Process



Stakeholder Outreach

Stakeholder Outreach Efforts		
June 2018		
25 June 18	Met with Commerce RI	
26 June 18	Met with RIDOT	
28 June 18	Met with Town of West Warwick	
July 2018		
10 July 18	Met with City of Warwick	
12 July 18	Met with Town of East Greenwich	
19 July 18	Met with Quonset Development Corporation	
August 2018		
7 Aug 2018	Met with Central RI Chamber	
27 Aug 18	Met with East Greenwich Chamber	
28 Aug 18	Met with Electric Boat	

Stakeholder Outreach Efforts		
November 2018		
29 Nov 18	Met with Town of East Greenwich	
31 Nov 18	Letter mailed to project abutters to attend Open House	
December 2018		
4-10 Dec 18	Ads promoting Public Open House placed in three newspapers	
11 Dec 18	Public Open House at New England Institute of Technology	
February 2019		
13 Feb 19	EFSB Hearing, New England Institute of Technology	
25 Feb 19	EFSB Hearing, West Warwick High School	
March 2019		
11 Mar 19	East Greenwich Town Council	

Committed to On-Going Communication


Multiple ways for stakeholders to communicate with the project team

Call our 24-hour hotline: **401-234-1138** or **877-423-1803**

Send us an Email: info@growthpointri.com

Follow the project on Twitter: (will launch when construction starts)

@growthpointri



Project website https://growthpointri.com/

GrowthPoint

nationalgrid

RELIABLE NATURAL GAS FOR SOUTHERN RI